BRUHAT BANGALORE MAHANAGARA PALIKE
RAJARAJESHWARINAGARA ZONE,
Project Division.

SCHEDULE - B

Name of Work :Providing Developmen of Slab Drain From 15th Cross to SWD Drain Inside J.P Park in Ward No 17 RRN Zone.

Tender Notification No: BBMP/EE/Proj/TEN/04/2012-13,Date: 28-06-2012 Item No.17

Sl. No.	Description	Unit	Qty	Rate(Rs.) in	
				Figure	Words
1	Earthwork in surface excavation in Hard soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications.	Cum	241.75	165.33	Rupees One Hundred Sixty Five and Thirty Two Paise Only
2	Earthwork excavation for foundation of buildings, water supply sanitary lines and electrical conduits either in pits or in trenches 1.5m. In and above in width, in hard soil not exceeding 1.5m in depth including dressing in bottom and sides of pits and trenches, stacking the excavated soil clear from edges complete as per specifications. and as per the direction of the engineer in charge specifications. and as per the directions of the engineer in charge of the work	Cum	579.10	207.83	Rupees Two Hundred Seven and Eighty Three Paise Only
3	Providing and laying in position plain cement concrete of mix M15 with OPC cement @ 240kgs, with 40mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregtes @ 0.459cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	72.12	4330.22	Rupees Four Thousand Three Hundred Thirty and Twenty Two Paise Only
4	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete.	Cum	96.00	509.57	Rupees Five Hundred Nine and Fifty Seven Paise Only
5	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	308.16	3380.15	Rupees Three Thousand Three Hundred Eighty and Fifteen Paise Only
6	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Sqm	513.60	75.08	Rupees Seventy Five and Seven Paise Only

o.	Description	Unit	Qty	Rate(Rs.) in	
				Figure	Words
7	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregtes @ 0.459cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.	Cum	38.51	5493.18	Rupees Five Thousand Four Hundred Ninety Three and Seventeen Paise Only
8	Providing and TMT steel reinforcement for R.C.C work including straighterening, cutting, bending, hooking palcing in position, lapping and /or welding wherever required, tieing with binding wire, anchoring to the adjoining members wherever necessary, as per desing (laps, hooks and wastage shall not be measured and paid) cost of all materials, labour, HOM of machineries complete as per specifications.	Qtl	12.84	7678.67	Rupees Seven Thousand Six Hundred Seventy Eight and Sixty Six Paise Only
9	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness above 200 mm including cost of all materials, labour complete as per specificaitor.	Sqm	63.25	330.65	Rupees Three Hundred Thirty and Sixty Five Paise Only
10	Fabricating, Supplying and erecting to Plumb and line, Stainless steel pipe railings as per approvid drawings using 75mm square 14 gauge pipe for verticals and neatly grinded. SS cups on either S.S pipe welded to the square Pipe. Two plates 10mm thick welded at bottom for base grip. All the joist welding including grinding, Finishing, matel patty and painting two coats of Fountion of size 0.30x0.30x0.60 and filling with C.C 1:2:4. The sets are inclusive of all materials, job work, Loding unloding etc., complete. The work should be carried as per the drawing and directions of the Enginee-in-Charge of the work.	Rmt	15.00	6238.58	Rupees Six Thousand Two Hundred Thirty Eight and Fifty Seven Paise Only
11	Loading and unloading of stone Boulder / stone aggregate /Sand/Kanker/Moorum. KSRRB M100-1: Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications, Cost of Haulage Excluding and unloading	Cum	635.00	92.06	Rupees Ninety Two and Five Paise Only

Signature of contractor

Executive Engineer
Project Division, R.R.Nagara Zone,
Bruhath Bangalore Mahanagara Palike